

LTR Lifts & Escalators Ltd, Graphic House, Druid Street, Hinckley, Leicestershire, LE10 1QH
Tele – 01455 633760; Fax – 01455 636005; E-mail – sales@ltr-lifts.co.uk; Web – www.ltr-lifts.co.uk

LTR MODEL EQUIPMENT SPECIFICATION

Schedule of Attendances & Associated Works – Reference: E-ATT-01

The following details the associated works required for the installation of Escalators provided by both LTR Lifts & Escalators, and Others.

For further information or assistance please contact LTR Lifts & Escalators;
Tele 01455 633760; or E-mail – sales@ltr-lifts.co.uk

SCHEDULE OF ATTENDANCE'S TO BE PROVIDED (if applicable)

PROVIDED BY LTR LIFTS & ESCALATORS

- Liase with Police and Local Authorities regarding transportation and access to site.
- Cranage to off load at site (subject of P.C. sum included in standard price)
- Labour for off loading and manoeuvre of Escalators to the finally installed position.
- Lifting Equipment (chain blocks and slings only).

PROVIDED BY OTHERS

1. Calculations with regard to the building.
2. Builder's work such as forming the well, pit and/ or machine room to interface with the escalator dimensions as detailed on LTR General Arrangement Drawings.
3. Cutting away and making good.
4. Site painting after installation other than bright parts or factory finished surfaces)
5. Treatment of escalator area to inhibit the formation of dust.
6. Suitable lifting and pulling points to suit LTR's requirements.
7. Levels for sizing of escalators.
8. Any reinforcement necessary for load bearing together with properly located supports of adequate strength for truss at upper and lower landings, and intermediate supports.
9. Any necessary drainage, tanking, lining or reinforcing of escalator area.
10. Guarding of openings and other measures necessary to ensure the safety and convenience of the occupants and other personnel within the building.
11. Scaffolding, load bearing platforms, planks, ladders and temporary screening to LTR requirements.
12. Storage of materials, tools and clothing in a suitably locked dry, heated and illuminated storage space protected from theft and damage.
13. Suitable temporary and permanent power supplies for tools and equipment, shutters and the operation of the Escalators in accordance with an agreed programme.
14. Mess rooms, sanitary accommodation and welfare facilities.
15. A roadway or equal immediately adjacent to the building entrance where off-loading will take place. The reinforcement of paving and floors, making suitable access.
16. Provision of ramping, protection and all necessary access space for unloading, hoisting or lowering of the escalator, in or outside the building or within the escalator well and for the handling to its final position.
17. Suitable floor openings, properly framed and finished in accordance with LTR's drawings, all permanent enclosures, shutters, railings, sprinklers and smoke baffles for the escalator area that may be required.
18. Proper covering of the escalator for protection against damage and contamination until acceptance. Cleaning down, renewal or replacement of equipment damaged by dust produced from other contractor's processes such as dry grinding of mosaic and other builders work.
19. As may be necessary for escalators installed in the open, working scaffolding of proper height and temporary screening around the Passenger Conveyor, consisting of a working weatherproof cover with heating if necessary, for the protection of the workmen concerned. The provision of drains connected to the lower outlet end of drip trays capable of dealing with the most abnormal rainfall.
20. Extra costs due to surveyor's fees or special requirements of government departments, local authorities, insurance companies consultants other bodes or officials.
21. Provision of safe and adequate access to the site and escalator area to the satisfaction of the Health & Safety at Work Act.
22. Provision for taking on any of the roles specified in the C.D.M. Regulations other than that of 'Contractor'.

